

Santa Felicia Dam Safety Improvement Project




Location:

The project is located at the Santa Felicia Dam, at the southern edge of Lake Piru Reservoir, approximately 4½ miles northeast of the unincorporated town of Piru in Ventura County, California, and is in a moderately active seismic region of Southern California. Constructed in 1954-1955 by UWCD, the dam provides storage for local runoff and imported State Water used for sustainable groundwater recharge and direct delivery of water supplies within UWCD's service area, as well as seawater intrusion abatement and water quality improvement in the Oxnard Plain.

Project Description:

Santa Felicia Dam is categorized as an extremely high hazard dam due to the large population residing directly within the dam inundation zone. The project consists of construction of a new outlet works, including a small hydropower facility, designed to withstand the Maximum Credible Earthquake, estimated to be a magnitude 7.2 earthquake. Additionally, the project includes raising the dam crest by 6½ feet and modifications to the existing spillway, resulting in an increased hydraulic capacity of the spillway in order to safely pass the inflow design flood and prevent overtopping the spillway walls.



BENEFITS/YIELD

- Improvements to the aging outlet works and spillway increase the resilience of Santa Felicia Dam, reducing the risk to public safety causing dam failure and downstream flooding.
- Minimizing catastrophic dam failure will protect against potential loss of life, injuries, and damage to the downstream communities with a combined population of nearly 400,000 residents along the Santa Clara River Valley.
- The new outlet works secures continued operational flexibility for sustainable groundwater recharge and direct delivery of water supplies within UWCD's service area, thereby increasing resilience of the region's water supply and water sustainability and helping over drafted conditions of groundwater basins.
- The project ensures continued habitat releases to lower Piru Creek. A new release channel connecting discharges from the new outlet works to the existing lower Piru Creek channel will provide high quality spawning and rearing habitat for Southern California steelhead in lower Piru Creek, which is designated critical habitat to the endangered species.
- Modernization allows continued operation of the dam's hydropower facility, which in part may help control invasive quagga mussels released into Lower Piru Creek during low flow releases.
- The new outlet works will provide operational flexibility and redundancy in operations, allow for selective withdrawal of reservoir water at various elevations for water quality management purposes, and accommodate future sediment level rise in the reservoir.
- The project will create new construction job opportunities. The estimated daily need for skilled laborers ranges from 37 to 46 workers.





United Water
CONSERVATION DISTRICT

Santa Felicia Dam Safety Improvement Project

Estimated Cost:

The Santa Felicia Dam Safety Improvement Project will be completed at an estimated cost of \$151 million.



NOAA
FISHERIES

Current/Potential Partners:

State Department of Water Resources Division of Safety of Dams, Federal Energy Regulatory Commission and National Marine Fisheries Service.

Current/Potential Funding Sources:

- \$68 million – FEMA Hazard Mitigation Grant Program – FEMA Hazard 404 to support the design and construction of the new outlet works
- \$63.7 million – EPA Water Infrastructure Finance and Innovation Act (WIFIA) low-interest loan to support both project components
- \$163,000 – High Hazard Potential Dam (HHPD) Rehabilitation Grant program

Ask from United to Regulators, Legislators, Local Agencies, and Stakeholders:

Continued support and guidance to improve earthquake resilience and flood safety.

